

Help Shape This Project!

Share your feedback, and visit pickering.ca/KrosnoCreek

Krosno Creek Stormwater Management Facility K-16

Date: April 28th, 2026

Irina Marouchko, P.Eng.,
Project Manager
City of Pickering




Will Cowlin, P.Eng., CAN-CISEC
Project Manager
Aquafor Beech Limited



History and Background

- ❑ Stormwater runoff from roads, including Highway 401, carry salt, oil and debris, and other pollutants into local waterways.
- ❑ The Frenchman's Bay Watersheds Stormwater Management Master Plan (FBSWMMP) prepared by MMM Group Ltd. (2009) identified that uncontrolled stormwater runoff into the Bay has led to a decline in water quality over time, negatively impacting the local ecosystem.
- ❑ SWM Facility K-16 was identified in the FBSWMMP as an opportunity to improve water quality control.
- ❑ Krosno Creek is one of the main four tributaries of Frenchman's Bay and was recommended for water quality control through an End-of-Pipe (EOP) facility or alternative.






Alderwood Park

- ❑ Located at the eastern end of Wharf Street.
- ❑ Existing use is an open green space with unofficial walking paths.
- ❑ Borders the Frenchman's Bay coastal wetland complex.
- ❑ Contains an existing uncontrolled outlet into Frenchman's Bay.

Project Goals and Progress


Here are the goals of the SWM Facility K-16 :



Enhanced water quality control to protect Provincially Significant Wetlands (PSWs) in Frenchman’s Bay.



Maintain a safe outdoor space that can continue to be used by community members.



Planting trees and a mixture of native and pollinator plants to improve biodiversity in the park.

SWM Facility K-16 Project Timeline:



- ✓ Frenchman’s Bay SWM-MP
- ✓ Project Goals
- ✓ Alderwood Park Site Chosen

- ✓ Feasibility Assessment
- ✓ Site Investigations
- ✓ Conceptual Design Chosen


We are here!

- Final Design Development
- Construction Procurement

- Mobilization
- Construction Works
- Restoration

What is an End-of-Pipe Facility?

- ❑ Stormwater runoff from a neighbourhood or catchment area is routed to a centralized End-of-pipe (EOP) facility before it is released to a natural watercourse.
- ❑ EOP Surface facilities are designed for water quality control to comply with the Ministry of the Environment, Conservation and Parks guidelines.



EOP Wet Pond Facility


EOP Alternatives

- ❑ Aquafor completed the Krosno Creek SWM Feasibility Assessment (2025) to evaluate the three (3) EOP surface facilities.
 - ❑ **Wet Pond:** A deep open-water pond, containing a Forebay and a Main Cell. These facilities have a typical maximum depth of 2.0m.
 - ❑ **Wetland:** A shallow and densely vegetated wetland, containing a Forebay and a Wetland Cell. These facilities typically have a maximum depth of 1.0m and 0.3m in each component respectively.
 - ❑ **Hybrid Pond:** A combination of a deep open-water Forebay and a shallow Wetland Cell. These facilities typically have a maximum depth of 2.0m and 0.3m in each component respectively.



EOP Wetland Facility

Alternative #1: EOP Wet Pond



Alternative #2: EOP Hybrid Pond














FIGURE 4-3: HYBRID FACILITY CONCEPTUAL LAYOUT













Alternative #3: EOP Wetland



Design Alternative Evaluation

SWM Approach	Social/Cultural		Economic	
	Public Health & Safety	Accessibility to Informal Trails	Capital Cost	Maintenance Cost
EOP Wet Pond			\$1.3 – 1.7 million	
EOP Hybrid Pond			\$1.2 – 1.5 million	
EOP Wetland			\$1.0 – 1.3 million	

SWM Approach	Overall Ranking
EOP Wetland	1 st
EOP Hybrid Pond	2 nd
EOP Wet Pond	3 rd

SWM Approach	Natural Environment		Technical Feasibility	
	Water Quality Improvement	Risk of PSW Encroachment	Required Footprint	Construction Complexity
EOP Wet Pond				
EOP Hybrid Pond				
EOP Wetland				

LEGEND	
	Best Performance
	Good Performance
	Average Performance

Construction Expectations

Working Hours

Construction work will take place Monday to Friday between the hours of 7:00am to 7:00pm. Extended hours will be on an as needed basis as approved by the City.

Closures to trails and sidewalks

Trails and sidewalks along the construction access will be closed during construction. Buses and emergency services will be notified of construction as required.

Disturbance

Noise, dust, mud and vibrations should be expected. We have taken precautions to limit disturbance as much as possible.



Site Access

Site access to Alderwood Park via Wharf St. from Liverpool Rd.

Total Truckloads

25-50 trucks per day during peak hauling times (3-4 weeks, intermittent).

General Construction Timing

Anticipated Start: Spring 2027.
Anticipated Finish: Winter 2027.
Estimated to take 6-10 months to complete. City will provide notification on start dates closer to construction.

Anticipated Haul Route:

Westbound: Liverpool Road to Highway 401.
Eastbound: Liverpool Road to Bayly Street to Brock Road to Highway 401.